

2024 Illinois Association of Floodplain and Stormwater Managers

Knollwood Flood Mitigation Project

Raise the Road!

Fox Lake, IL

Michael Warner, PE, CFM, DECI



Susan Novak, PE
Director Of Public Works
Village of Fox Lake



Wadee Rafati, PE






Raise The Roof | Uncle Luke | Choreography by Bethany Hall



Copy link



Where



IL Route 59



Roadway Improvement
- Ellivert Road (Approx. 741 ft)
- Existing

1 inch = 100 Feet



Knollwood - what is happening to the roads?
 Soils - loose organic silt/peat over 20' deep in some spots
 Roads compacting/subsiding over a long period of time




Comments:

depth, ft.	Equipment: <input type="checkbox"/> D - 25 <input checked="" type="checkbox"/> D - 50 <input type="checkbox"/> Hand Auger <input type="checkbox"/> Other
	CLASSIFICATION
Elevation	Existing Surface
0	Black organic silt, some gravel, trace sand, damp-very damp, very loose - Fill
5	Dark brown-black organic peat, trace shells, very damp, very loose
10	
15	Brown-gray organic silt, trace shells, very damp, very loose
20	Gray fine sand, trace medium-coarse sand, saturated, very loose to loose
25	Gray fine sand, some medium-coarse sand, trace gravel, saturated, medium dense
30	End of Boring
35	
40	



Lake County and around Fox Lake have vast areas of hydric soils



- A. The restoration fill shall meet pre-subsidence elevations, and within riverine areas, the pre-subsidence effective Regulatory Floodplain and Regulatory Floodway conveyance shall be maintained.

What was the key elevation?

<u>Flooding Source and Location</u>	<u>Elevation (feet NAVD 88)</u>			
	<u>10-Percent- Annual-Chance</u>	<u>2-Percent- Annual-Chance</u>	<u>1-Percent- Annual-Chance</u>	<u>0.2-Percent- Annual-Chance</u>
Nippersink Lake (including Dunns Lake)	739.4	740.7	741.3	742.5

- ▶ 741.00 to provide 100-year protection
 - ▶ Access to homes can be maintained during the 100-year event at elevation 741.00
 - ▶ 0.3' makes a difference in design and price

Why The Problem - It floods







Knollwood Homes Raised above BFE



Additional flood mitigation - Knollwood Residential Buyouts

2 homes remediated by Lake County Stormwater Management Commission buyout program



623 Channel Lane




200 Park Lane



When did - it flood?

- ▶ Flood events - how bad was it?
- ▶ Knollwood Road impassable = 6.5-7
- ▶ June 2008 - 7 days
- ▶ April 2013 - 10 days
- ▶ July 2017 - 14 days



Who was involved

- ▶ Knollwood Neighborhood Residents - rallied officials, assisted with easements
- ▶ Village of Fox Lake - elevated flooding concern, lobbied for project, easements
- ▶ Lake County Stormwater Management Commission - sought grants, worked with stakeholders



- ▶ Illinois State Representatives and Senators - appropriated funding, prioritized flood mitigation
- ▶ IL Department of Commerce and Economic Opportunity - grant funding and project management
- ▶ Governor J.B. Pritzker's Office - supported budgeting and prioritization



- ▶ Gewalt Hamilton Associates - project design, construction, SE/SC monitoring
- ▶ Maneval Paving Company - construction contractor, under contract time and under budget



DCEO and More Acronyms

- ▶ Department of Commerce and Economic Opportunities
- ▶ BEP MBE/WBE/DBE - Is it a goal or requirement?
- ▶ Monthly Reporting Requirements
 - PPR & PFR
 - Cancelled Checks
 - Payment Applications with Waivers



Stormwater
MANAGEMENT COMMISSION
LAKE COUNTY, IL



When did -

- ▶ **Funding - Announced November 2021**
- ▶ **GHA Design - Winter 2021**
- ▶ **Public Outreach/Neighborhood Meeting - January 2022**
 - ▶ **Begin easement outreach**

When did -

- ▶ Easements ultimately finalized (during construction)
- ▶ Ongoing right of entry/easement webapp
- ▶ [Knollwood Easement App](#)



Layer List

Layers

- ▶ Easement Received?
- ▶ Right of Entry Received?

When were -

Permits issued

- ▶ **USACE (June 2022)**
- ▶ **LCSMC (June 2022)**
- ▶ **IDNR-OWR (Delegated project to LCSMC)**
- ▶ **IDNR EcoCAT and Wetland Impact signoff “minimal alteration”**
- ▶ **IEPA SP3, NOI 5/2022, NOT 5/2023**

The following special conditions are a requirement of your authorization:

1. This authorization is contingent upon implementing and maintaining soil erosion and sediment controls in a serviceable condition throughout the duration of the project. You shall comply with the Lake County Stormwater Management Commission (LCSMC)'s written and verbal recommendations regarding the soil erosion and sediment control (SESC) plan and the installation and maintenance requirements of the SESC practices on-site.

- a. You shall schedule a preconstruction meeting with LCSMC to discuss the SESC plan and the installation and maintenance requirements of the SESC practices on the site. You shall contact the LCSMC at least 10 calendar days prior to the preconstruction meeting so that a representative may attend.
- b. You shall notify the LCSMC or the LCSMC's designated agent of any changes or modifications to the approved plan set. Field conditions during project construction may require the implementation of additional SESC measures. If you fail to implement corrective measures, this office may require more frequent site inspections to ensure the installed SESC measures are acceptable.
- c. Prior to commencement of any in-stream work, you shall submit construction plans and a detailed narrative disclosing the contractor's preferred method of cofferdam and dewatering method to the LCSMC or the LCSMC's designated agent. Work in the waterway shall NOT commence until the LCSMC notifies you, in writing, that the plans have been approved.

Permits issued - LCSMC Determined as "Public Flood Control Project"




Exhibit 2 - Flood Height Analysis
Knollwood Subdivision Flood Mitigation

Wetland Impacts

- ▶ Initial design > 0.1 acre impact = mitigation need
- ▶ Design refinements < 0.1 acres of permanent impact
- ▶ Both Corps (0.092 ac) and Isolated wetlands (0.008 ac)
- ▶ Maintain hydrology for Isolated wetland





▶ **SE/SC Critical**

- ▶ **Construction within wetlands (temporary and permanent impacts)**
- ▶ **Entire site an arm's length away from Duck Lake**
- ▶ **Several overland flow paths and culverts to install**
- ▶ **Long construction timeline expected**
- ▶ **Likelihood of another flood fairly high?**

When was -

Designated Erosion Control Inspector (DECI) Duties

Lake County DECI mirrors the IEPA ILR10 requirement minimums

Pre-construction meeting - 8/8/22

Initial SE/SC installation to DECI closeout 8/15/22 - 5/23/23

40-week active DECI period

35 - GHA DECI Inspections (formal reports)

2 - McHenry-Lake Soil and Water Conservation District Inspections (IEPA-NPDES Based)

11 - Lake County SMC SE/SC Inspections


8 - additional LCSMC resident engineer coordination meetings

When was -

Precipitation, total, inches

- ▶ 15 > 0.5” Precipitation Triggered Inspections
- ▶ USGS Nippersink+CoCoRhas Monitoring
- ▶ Typically LCSMC inspections followed precip events, or major project stages

USGS 05548280 NIPPERSINK CREEK NEAR SPRING GROVE, IL



— Daily sum precipitation — Period of approved data

Coir logs moved and replaced



When was the use of coir fibers for construction purposes first **documented** ?

- A. Third century B.C.
- B. First century A.D
- C. 11th century A.D.
- D. In the movie Castaway with Tom Hanks




Entrance road cross culvert

Cofferdam method:

Used plastic-wrapped concrete block





Flooding Source and Location

	Elevation (feet NAVD 88)			
	10-Percent-Annual-Chance	2-Percent-Annual-Chance	1-Percent-Annual-Chance	0.2-Percent-Annual-Chance
Nippersink Lake (including Dunns Lake)	739.4	740.7	741.3	742.5

OVERALL PLAN

PROJECT NO. 15

DATE

QllaOf-05-ZZ

21

a, 104-


Design Challenges

- ▶ How are we going to raise the road 2+ feet?
- ▶ Existing Road Geometry
- ▶ The Entrance
 - ▶ Wetlands
 - ▶ Soil Conditions
- ▶ Heavy impact on private property
 - ▶ Driveways and connecting slopes
 - ▶ Grading off edge of new roadway
- ▶ Drainage
 - ▶ How to maintain existing drainage patterns when you're building a dam in the middle of a subdivision
- ▶ Utility Conflicts
 - ▶ Aerial Wires??
- ▶ Construction Sequencing

How are we going to raise the road? - Typical Section

TYPICAL CROSS SECTION LEGEND

- NO DESCRIPTION
- (A) EXISTING GROUND
 - (B) EXISTING HMA PAVEMENT, VARIES 2.0"–5.75"
 - (C) EXISTING SUB BASE, VARIES 7.75"–38.5"
 - (D) FULL DEPTH RECLAMATION 10"
 - (E) EARTH EXCAVATION (FOR PAVEMENT WIDENING) (WIDTH VARIES)
 - (F) HOT-MIX ASPHALT SURFACE REMOVAL, 2"
 - (1) HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N50 (2")
 - (2) HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 (3")
 - (3) AGGREGATE SUBGRADE IMPROVEMENT, 12" (& VARIES)
 - (4) AGGREGATE SHOULDER TYPE B 5"
 - (5) RECLAMATION (SPREAD EVENLY AND REGRADED)
 - (6) PROPOSED FILL PGE, VARIABLE DEPTH
 - (7) EMBANKMENT FILL
 - (8) GEOTEXTILE FABRIC
 - (9) GUARDRAIL
 - (10) CA-1, VARIABLE DEPTH
 - (11) TOPSOIL FURNISH AND PLACE, VARIES (4" MIN.)
SEEDING, CLASS 2A
NITROGEN FERTILIZER NUTRIENT
POTASSIUM FERTILIZER NUTRIENT
EROSION CONTROL BLANKET
- ^R ITEM TO BE REMOVED



KNOLLWOOD ROAD RECONSTRUCTION
PROPOSED TYPICAL SECTION
STA. 104+50 TO STA. 108+75

Core	HMA Surface (in.)	HMA Binder (in.)	Total HMA (in.)	Granular Base (in.)	Total Pavement (in.)
<u>Spring Rd.</u>					
1	1.5	1.5	3.0	19.0	22.0
2	1.75	1.5	3.25	7.75	11.0
3	1.75	1.75	3.5	11.25	14.75
4	1.5	---	1.5	28.5	30.0
5	3.0	---	3.0	12.75	15.75
<u>Park Ln.</u>					
6	3.5	---	3.52	38.5	42.0
7	3.0	2.75	5.75	18.25	24.0
<u>Knollwood Rd.</u>					
8	2.5	3.0	5.5	30.5	36.0
<u>Channel Dr.</u>					
9	1.25	2.25	3.5	11.5	15.0
<u>S. Knollwood Rd.</u>					
10	0.75	1.75	2.5	14.75	17.25
11	2.0	---	2.0	28.0	30.0
12	1.5	1.5	3.0	13.0	16.0

Reclamation of pavement in-place





Reclaimed pavement compacted for base



Geotextile installation - the Secret Ingredient for the SE/SC




The Subdivision Entrance




KNOLLWOOD ROAD RECONSTRUCTION
PROPOSED TYPICAL SECTION
 STA. 101+35 TO STA. 104+50

Boring	Soil Type	Depth Below Existing Surface (feet)	Cohesion (psf)	Φ (deg)	Soil Unit Weight (Wet) (pcf)	Lateral Earth Pressure Coefficients	
						Active	Passive
Knollwood Road							
102	Fill	1.0 to 11.0	0	32	110	0.31	3.25
	Organic	11.0 to 27.0	50	10	80	0.70	1.42
	Granular	27.0 to 32.5	0	32	120	0.31	3.25
	Cohesive	32.5 to 36.0	1,250	20	115	0.5	2.0
	Granular	36.0 to 40.0	0	32	130	0.31	3.25



OPTION 1A
TIED 50 WIER PILE WALL



OPTION 1B
TIED SHEET PILE WALL



Two Piette Place, Suite 1400
 Ilasca, Illinois 60143
 Tel: 630.773.3900
 www.civiltechinc.com

EXHIBIT

KNOLLWOOD ROAD
 STRUCTURE OPTIONS

**KNOLLWOOD ROAD RETAINING WALL OPTIONS
CONSTRUCTION COST ESTIMATES**

Structural options too expensive

Used lightweight fill instead

Subsoil is peat > 20' deep

May need to fill again in the distant future

Option 1A - Tied Soldier Pile Wall with Light-Weight Fill					
Code No.	Item	Unit	Quantity	Unit Price	Cost
50800205	Reinforcement Bars, Epoxy Coated	Pound	33,900	\$2	\$50,850
50901050	Steel Railing, Type SM	Foot	500	\$225	\$112,500
52200900	Concrete Structures (Retaining Wall)	Cu. Yd.	226.0	\$850	\$192,100
X0325318	Lightweight Cellular Concrete Fill	Cu. Yd.	805.6	\$120	\$96,672
X0325751	Driving Soldier Piles	Foot	1,820	\$1	\$1,820
Z0046304	Furnishing Soldier Piles (HP Section)	Foot	1,820	\$85	\$154,700
Z0075400	Tie Rods	Each	52	\$365	\$18,980
	Cofferdam / Dewater	Each	2	\$20,000	\$40,000

Sum of Estimated Items ■ \$667,622
20% Other Items ■ \$133,524
Total ■ \$801,100

Option 1B - Tied Sheet Piling					
Code No.	Item	Unit	Quantity	Unit Price	Cost
50800205	Reinforcement Bars, Epoxy Coated	Pound	28,340	\$2	\$42,510
50901050	Steel Railing, Type SM	Foot	500	\$225	\$112,500
52200900	Concrete Structures (Retaining Wall)	Cu. Yd.	188.9	\$850	\$160,565
52200015	Permanent Sheet Piling	Sq. Ft.	15,000	\$50	\$750,000
Z0075400	Tie Rods	Each	52	\$365	\$18,980

Sum of Estimated Items ■ \$1,084,555
20% Other Items ■ \$216,911
Total ■ \$1,301,500

Option 2 - Land Bridge					
Code No.	Item	Unit	Quantity	Unit Price	Cost
50300225	Concrete Structures	Cu. Yd.	84.3	\$900	\$75,870
50300255	Concrete Superstructure	Cu. Yd.	357.5	\$1,200	\$429,000
50800205	Reinforcement Bars, Epoxy Coated	Pound	91,050	\$2	\$136,575
50901050	Steel Railing, Type SM	Foot	500	\$225	\$112,500
51200957	Furnishing Metal Shell Piles 12" X 0.250"	Foot	3,000	\$60	\$180,000
52200900	Concrete Structures (Retaining Wall)	Cu. Yd.	74.1	\$850	\$62,985
	Cofferdam / Dewater	Each	2	\$20,000	\$40,000

Sum of Estimated Items ■ \$1,036,930
20% Other Items ■ \$207,386
Total ■ \$1,244,300

Option 3 - MSE Wall with Conc. Column Ground Improvement					
Code No.	Item	Unit	Quantity	Unit Price	Cost
50800205	Reinforcement Bars, Epoxy Coated	Pound	17,790	\$2	\$26,685
50901050	Steel Railing, Type SM	Foot	400	\$225	\$90,000
52200500	MSE Retaining Wall	Sq. Ft.	1,468	\$100	\$146,800
52200900	Concrete Structures (Retaining Wall)	Cu. Yd.	118.6	\$850	\$100,810
	Concrete Column Ground Improvement	Sq. Ft.	8,840	\$30	\$265,200
	Cofferdam / Dewater	Each	2	\$20,000	\$40,000




Sum of Estimated Items ■ \$669,495
20% Other Items ■ \$133,899
Total ■ \$803,400




Things to consider for construction

- ▶ **Construction staging areas**
- ▶ **Construction Sequencing**
- ▶ **Road closures**
- ▶ **Material removal and material delivery**
- ▶ **Mail delivery, garbage pickup, etc...**
- ▶ **Emergency Vehicle Access**
- ▶ **Temporary Parking Areas**

Private Property Impact



Utility Conflicts



*Clearance requirements for aerial wires:
 16'-6" Minimum over all roads
 18' Minimum over IDOT Highway

NO.	BY	DATE	REVISION	NO.	BY	DATE	REVISION

FILE: 5380.014-wires PLG.dwg	SHEET NUMBER:
DRAWN BY: PJS	1
DATE: 02-07-22	
GHA PROJECT # 5380.014	OF SHEETS
CHECKED BY: MZ	SCALE: 1"=80'
DATE: 02-07-22	

PHASE 3:
 KNOLLWOOD RD
 ENTRANCE

PHASE 3:
 KNOLLWOOD
 RD/PARK LN/OAK LN
 ALLOWABLE CONSTRUCTION
 STAGING AREA

PHASE 1:
 SPRING ROAD

PHASE 2:
 KNOLLWOOD RD
 S/CHANNEL LN

SEQUENCING OF MAJOR ACTIVITIES:

The following recommended sequencing shall serve the purposes only as a general outline for the contractor to use to complete their detailed construction schedule. All changes or revisions shall be approved by the engineer before work is anticipated to commence.

1. Place temporary information signs, every (7) calendar days prior to construction commencement on each respective street segment.
2. Furnish and install erosion and sediment control devices, including all fence and inlet filter basins. Erosion control devices shall be installed at each roadway street prior to the start of any construction activities. The contractor shall also install any de-watering flags and polyfills required for the work.
3. Furnish and install tree protection or root pruning as shown on the plans or as marked by the engineer.
4. Place temporary traffic control and protection measures.
5. Perform utility work.
6. Perform road construction as shown in Road Construction Sequencing Notes.
7. Perform drainage valve work.
8. Temporarily stabilize the construction area and perform restoration.
9. Permanently stabilize the construction area.
10. Remove temporary erosion control measures and trees protection fencing once vegetation has been established.
11. Complete all general land-PC restoration.
12. Perform street sweeping operations within the project limits and adjacent roadways.
13. Remove temporary traffic control and protection measures.

Issues - Lessons Learned

- ▶ Easements - Early and Often, connect/outreach with residents
- ▶ ROE Agreements - same as above
- ▶ Never (if possible) change the “current” natural drainage pattern
 - ▶ (wetland hydrology especially)
 - ▶ Resident expectations
- ▶ Dealing with Residents
 - ▶ Make sure to explain the purpose of the project, and what the final product will be
- ▶ Utility conflicts
 - ▶ Wow these can be cumbersome, wires, poles, pipes, vaults

How much \$?

- ▶ Initial Estimate = \$2.7M
- ▶ Grant Amount = \$2.7M
 - ▶ \$2.1M Construction EOPC
 - ▶ \$300k Design Engineering
 - ▶ \$300k Construction Engineering
- ▶ Low Bid = \$2.3M
- ▶ Final Costs
 - ▶ \$1.8M Construction
 - ▶ \$270k Design Engineering
 - ▶ \$180k Construction Engineering
- ▶ \$450k savings!

Success! - Under budget and time!





Questions?