





Hart Ditch Improvements

Joint Project in Northwest Indiana






Plum Creek/Hart Ditch Watershed

Confluence with Little Calumet River
in Munster, IN

71 mi² at confluence with Little
Calumet River




Plum Creek/Hart Ditch Watershed

71 mi² at confluence with Little Calumet River

36 mi² drainage area in Illinois before it enters Dyer, IN

Water knows no boundaries!



US 30

Franciscan
Health Dyer


Hart Ditch

Berens Monaldi
Subdivision

Plum Creek


Flooding History

- November 1990
 - Significant flooding
 - 13 ft total rise
- August 2007 (saturated watershed)
 - 5" rain between 8/20 and 8/23
 - 1" in Dyer and 5" rain in Will Co. on 8/24
 - 9' rise in 18 hours
- September 2008 (Hurricane Ike)
 - 9" on the 13th and 14th
 - 8' rise in 18 hours



Event	Rainfall (in)	Peak Gage (ft)
Nov. 1990	~6"	13
Aug. 2007	10"	15.7
Sept. 2008	9"	16.8

Significant Flooding throughout Dyer from 2007 and 2008 events



- August 2007 had > \$4M in damages to homes
 - \$2.8M in Berens Monaldi subdivision
 - Cases of foundation collapses
 - Houses with 8 feet of water in the basement
 - \$33M in damages at Franciscan Health Dyer
 - Over 2' going through Emergency Room
- September 2008
 - More damages than Aug. 2007



Significant Flooding throughout Dyer from 2007 and 2008 events



Photos of the Year 2007




JESSICA KOSCIELNIAK/ THE TIMES
Flood waters at St. Margeret Mercy in Dyer , Indiana.

Photo is looking south from US 30




Flood Mitigation and Alternatives Measures

- Lake County Surveyor's Office commissioned a study of the watershed
 - Plum Creek Hart Ditch Watershed Study
 - Hydrologic and hydraulic models of the watershed
 - Calibrated to long and short duration events
 - Verified using Jan. 2008 and Sept. 2008 events
 - Used for predicting flood events on anticipated rainfall
 - Larger flows than regulatory flows (3389 cfs vs 1910 cfs)
- Added rain gage in Goodenow (2009)
- Added a stream gage on Plum Creek (2009)
- Emergency Action Plan




Gages Added in Plum Creek Watershed

- USGS Rain Gages
 - Hart Ditch at 213th Street in Dyer
 - Crete, IL
 - Goodenow, IL (new)
- USGS Stage Gages
 - Hart Ditch at 213th Street in Dyer
 - Plum Creek (new)



Warning Stage - 213th Street Gage, Dyer



Predictions and Emergency Response

Used for predictions

Correlation between stage gages

Time to prepare for floods and enact emergency actions


Flood Mitigation and Alternatives Measures



- Longwood Golf Course in NW corner of Will County
- Widen Hart Ditch
- Multiple smaller storage areas
- Berms to protect subdivision and hospital

Flood Mitigation and Alternatives Measures

- Longwood Golf Course in NW corner of Will County
- Widen Hart Ditch
- Multiple smaller storage areas
- Berms to protect subdivision and hospital



Franciscan
Health Dyer


Berens Monaldi
Subdivision

Flood Mitigation and Alternatives Measures

- Berens Monaldi Subdivision berms and pump station paid for by Town of Dyer
- Franciscan Health Dyer berms paid for by the hospital








- Flood protection elevations determined using calibrated modeling
- Flood walls provide protection elevation greater than the elevations from the September 2008 storm event

Flood Mitigation and Alternatives Measures Implemented

- Town of Dyer
 - In excess of \$2,800,000
- Franciscan Health Dyer
 - In excess of \$1,000,000
- Updated Stormwater Ordinance
- Search for storage projects using “compensatory storage” requirements from berms
- Longwood golf course project was studied in detail



- CHALLENGES
 - Uncooperative sellers
 - Significant permitting issues
 - Will County FPD
 - Cost

Storage (ac-ft)	Cost (\$M)	Reduction at Hart St (ft)
330	7	0.4
670	12.8	1.3
1020	21	1.8

Flood Mitigation and Alternatives Measures

- Town of Dyer
 - In excess of \$2,800,000
- Franciscan Health Dyer
 - In excess of \$1,000,000
- Updated Stormwater Ordinance
- Search for storage projects using “compensatory storage” requirements from berms
- Longwood golf course project was studied in detail
- Identified 2-stage channel improvements

Cooperative Effort

- Town of Dyer
- Franciscan Health Dyer
- Lake County Drainage Board
- Little Calumet River Basin Development Commission
- Lake County Highway Department



Cooperative Effort

- Awarded bid - \$1,856,309.78 to Dyer Construction, with change orders about \$1.9M
- Town paid \$1,090,880 for purchase of houses and demolition and tree clearing
- Total Cost was approximately \$3.3M
- Franciscan Health Dyer contributed \$2,047,118.22 (agreement from 2010)
- Little Calumet River Basin Development Commission contributed \$600,000
- Received grant from DNR Lake Michigan Coastal Program for \$100,000
- 3 Houses removed and land dedicated to Town from Lake County Highway Department
- Lake County Surveyor's Office funded initial watershed study and various alternative studies

An aerial photograph of the Franciscan Health Dyer area. A red dashed line outlines the hospital's perimeter. A red arrow points from a red box to this line. A blue dashed line follows a path through the area, with a blue arrow pointing from a blue box to it. A green dashed line follows a path through the area, with a green arrow pointing from a green box to it. A pink dashed line follows a path through the area, with a pink arrow pointing from a pink box to it. A yellow dashed line follows a path through the area, with a yellow arrow pointing from a yellow box to it. The map shows a mix of green space, roads, and buildings.

**Franciscan
Health Dyer
Flood Wall**

**Hospital still
susceptible to
flooding**

**Homes still
susceptible to
flooding**

**Berens Monaldi
Phase II Berm**



**Berens Monaldi
Phase I Flood Wall**

- **Why is Franciscan Health Dyer still interested in participating?**
- **Why is Town still interested in participating?**


Concept Design



Creating a 2-Stage Ditch: Existing and Proposed Section Views




SECTION 1-1 EXISTING PROFILE: Typical Existing Conditions (Looking East)



SECTION 1-1 PROPOSED PROFILE: 2-Stage Ditch with Reinforced Stream Bank Edge (Typical Conditions -- Looking East)

Site Conditions prior to design

- Video from February 21, 2018 after storm event
 - Berm protecting hospital
 - First area to flood is behind homes on west side of Hart Street
 - Large trees throughout project site
 - Potential overtop locations to the south (left in video)
 - Hart Street bridge is a 2 lane bridge
- Survae





Pictures from December 2021









Expected Project Benefits


- Water Quality and Quantity Benefits
 - Significantly improved ditch stability:
 - Bench area to be sloped towards ditch at 2%
 - After bench, bank sloped at 2:1 to maximize storage area
 - Toe of the ditch reconstructed as a preventive scour measure (rootwads and riprap) with vegetated mechanically stabilized earth bank above toe
 - J-hook and rock vane
 - Sediment reduction
 - Finer sediment particles will settle out on the bench areas
 - Coarser particles will form ditch bed



Expected Project Benefits

- Environmental
 - Bio-uptake of nutrients by vegetation located within the bench areas
 - The bench areas will filter pollutants and provide groundwater recharge
 - Native seed mix will provide wildlife habitat and accommodate migrating birds
- Educational
 - Kahler Middle School is 2 blocks from the site and students can walk to site to observe the results of the environmental restoration with native plants
 - Demonstration that 2-stage channel restoration can work in highly urban areas
 - Signage being installed explaining the project
 - Walking path

Design







Alternative protection for hospital

Install emergency concrete jersey barriers each time a flood was possible across entrances


Design to tie into hospital berm




Provides hospital needed protection



Design Cross-sections



Design Cross-sections




Tree removal in March 2022





New 3 lane Hart Street Bridge



March 21, 2022

Construction begins June 2022





Early July 2022












July 3, 2022



Early August 2022













Sept. 28, 2022 Photos

- Backflow preventors on all storm sewers
- Landcaping
 - Trees - 775
 - Shrubs - 500
 - Live stakes - 1,167

LEGEND

EXISTING STRUCTURE

EXISTING PROPERTY LINE

NEW CONTOURING

CONSTRUCTION LIMITS

SIDEWALK PAVEMENT

NEW TREES AND SHRUBS, 12' O.C.

NEW SHRUBS 12' O.C.

ROOTWAD REVEITEMENT

TURF REINFORCEMENT MATERIAL

VEGETATED MECHANICALLY STABILIZED EARTH BANK

4 PL1


1 PL1

2 PL1

3 PL1

6 MD4

4.5 MD1



ATTACH TREE TUBE TO STAKE AT TWO LOCATIONS WITH TIES

PLANTRA SUNFLEX GROW TUBE 1" I.D.

SET TOP OF ROOT MASS LEVEL WITH FINISH GRADE. PLANTS SHALL BE PLUMB AFTER SETTLEMENT.

3 GALLON TREE

VOIDS AROUND ROOTS TO BE BACKFILLED WITH SHREDDED TOPSOIL OR COMMON FILL AND COMPACTED BY FOOT

ADD 1/4 CUP OF TERRA-SORB MEDIUM GRADE (DRY) TO BOTTOM OF HOLE, (OR EQUAL)

AGRIFORM 31 GRAM LANDSCAPING TABLET TO BE BURIED BENEATH PLANT, NO CONTACT WITH ROOTS, (OR EQUAL)

WALLS OF HOLE TO BE VERTICAL

HOLE NOT TO BE DEEPER THAN ROOTS

PLANTRA TRUNK BUILDER FIBERGLAS STAKE 6"

1

CONTAINER TREE PLANTING DETAIL

NOT TO SCALE

MIXTURE OF TREES, SUBCANOPY TREES, AND SHRUBS. PLACEMENT TO BE APPROVED BY ENGINEER PRIOR TO PLANTING.

SHRUB (TYP)

NOTES:

1. TREES SHALL BE PLANTED AT 12'-0" ON CENTER.

2. SHRUBS SHALL BE PLANTED AT 12'-0" ON CENTER.

3. TREES AND SHRUB PLANTING SCHEDULE: SEPTEMBER 1ST TO DECEMBER 1ST OR UNTIL THE GROUND HAS FROZEN OR THE LATTER OF MARCH 1ST OR WHEN THE FROST LEAVES THE GROUND IN SPRING TO JUNE 1ST.

2

TREE AND SHRUB SPACING DETAIL

NOT TO SCALE

POINT BAR

ROOT WADS ORIENTED PERPENDICULARLY TO THE FLOW DIRECTION

FOOTER LOGS PLACED JUST BELOW STREAM BOTTOM. FOOTER LOG SHALL BE A MINIMUM OF 1'-0" IN DIAMETER AND SHALL BE A MINIMUM OF 5'-0" IN LENGTH

LIVE WOODY CUTTINGS

BRACING BOULDERS SHALL BE A MINIMUM OF 16" IN DIAMETER

PLAN

WRAPPED EARTH 900gram WOVEN COIR FABRIC

STREAM BOTTOM

BANKFULL ELEVATION

NATIVE EARTHEN MATERIAL

FOOTER LOG PLACED JUST BELOW STREAM BOTTOM. FOOTER LOG SHALL BE A MINIMUM OF 1'-0" IN DIAMETER AND SHALL BE A MINIMUM OF 5'-0" IN LENGTH

SECTION

TIE INTO EXISTING GRADE, MAX 2:1

SUPPORT BOULDER SHALL BE A MINIMUM OF 1'-0" IN DIAMETER

BACKFILL ON TOP OF ROOTWAD WITH COMMON FILL COMPACT TO FILL VOIDS

ROOTWAD WITH TRUNK BURIED INTO STREAM BANK. A MINIMUM OF 5'-0" TRUNK OF ROOTWAD SHALL BE A MINIMUM OF 1'-0" IN DIAMETER

3

ROOTWAD DETAIL

NOT TO SCALE

4' HMA PAVEMENT

PAVEMENT CROWN

6" COMPACTED AASHTO NO.53 AGGREGATE

12" COMPACTED AASHTO NO.53 AGGREGATE SHOULDER (TYP)

12" COMPACTED AASHTO NO.53 AGGREGATE SHOULDER (TYP)

4

SIDEWALK PAVEMENT DETAIL

NOT TO SCALE













Sept 20, 2022



Live Stake Planting – Dec. 13, 2022








Aerial video from Feb. 28, 2023

- <https://play.survae.com/?ll=41.49173550409626,-87.520862&z=17&mr=1&account=117&page=1&obj=BRbWjTOYpGnO&utc=1677608953842>

Benefits

- Walking path
- Access path for maintenance
- Stopped overtopping to the south
- Provided protection for the hospital
- Creates 14.5 acre-feet of online flood storage
- Lowers the WSEL up to 0.9 feet



Signage

Rootwads, J-Hooks, and Rock Vanes

What are they? Here are a few ways Hart Ditch/Plum Creek was transformed.




Water flowing through a community can be its most incredible beauty and a welcome asset.

Community leaders came together and embarked upon a multi-year project employing dozens of solutions and thousands of hours to transform Hart Ditch/Plum Creek into a beautiful natural asset.

A Do-Over

Top-to-bottom, side-to-side, Hart Ditch/Plum Creek needed a complete do-over. The earth along the creek was resculpted to ensure a healthy flow of water. Hundreds of native trees, shrubs, grasses, and wildflowers were planted along the waterway.

Rootwads, J-hooks, rock vanes, and 2-stage benches are also some of the many solutions used for the urban stream restoration of Hart Ditch/Plum Creek.



Healthy Neighborhoods Need Healthy Environments

We all live in neighborhoods

Our neighborhoods include...food, shelter, water, and safe places for us to grow.

Birds, mammals, fishes, aquatic creatures,

A local long-term solution was needed

For most of its history, Hart Ditch/Plum Creek could have been a better asset in the Town of Dyer. Upstream issues caused problems the Town of Dyer had no control over.

Sediment washed downstream, thickly coating the creek bed prohibiting a healthy environment. The waterway constantly overflowed its banks, causing repeated flooding of nearby homes and roadways, impacting the hospital grounds and buildings. There was no public access to the waterway as the banks were nearly vertical.

A local long-term solution was designed and implemented.



Before



After



Before




After

Project Partners:
Town of Dyer Stormwater Management Board
Lake County Surveyor's Office
Franciscan Hospital Dyer
Little Calumet River Basin Development Commission
Lake Michigan Coastal Program
Lake County Highway Department

The needs of small creatures were built into the project

The aquatic insects were given new homes with the riffles built into the creek, as well as fishes, and native crustaceans. The needs of migrating birds were considered in the planning. Many native trees, shrubs, grasses, and wildflowers were planted for birds and small mammals to rebuild healthy neighborhoods for their families. Butterfly gardens were designed and planted to care for the needs of pollinators such as butterflies, bees, and moths.

The art will be in color



The needs of people in the neighborhood were also considered

Walking paths and open spaces were built. Broad shallow flat areas were sculpted to hold floodwater long enough for them to calm down and slowly soak back into the earth - preventing flooding and recharging the super important aquifers below. Trees and shrubs were planted to create soft, healthy green spaces for everyone to enjoy.

Project Partners:
Town of Dyer Stormwater Management Board
Lake County Surveyor's Office
Franciscan Hospital Dyer
Little Calumet River Basin Development Commission
Lake Michigan Coastal Program
Lake County Highway Department



Questions?

