VILLAGE OF WILMETTE NEIGHBORHOOD STORAGE PROJECT The Largest Capital Project in the History of the Village

SPEAKERS

Brigitte Berger-Raish, PE Director of Engineering and Public Works, Village of Wilmette

Darren Olson, PE, CFM, D.WRE

Vice President, Assistant Department Head, Water Resources, Christopher B. Burke Engineering, Ltd.



Village of Wilmette Neighborhood Storage Project

> Overall Project Update December 2022







VILLAGE OF WILMETTE'S SEWER SYSTEMS

Princeton Place

VILLAGE OF WILMETTE'S STORM SYSTEM

SEPARATE SEWER AREA

- Developed 1930s and later
- Storm and sanitary flows in separate pipes
- Sanitary System flows to MWRD for treatment

Harms Road

- Stormwater conveyed by gravity to the Stormwater Pump Station
- Two discharge pipes to the North Branch of the Chicago River

COMBINED SEWER AREA

Combined Sewer Region

- Developed late 1800's to 1940's
- Storm and sanitary flows in the same pipes (Combined Sewer System)
 - Storm and Sanitary flows to MWRD for treatment

Ridge Road Divides the Combined Sewer Area and the Separate Sewer Area

WILMETTE HAD 5 STORMS IN RECENT HISTORY EXCEEDING A 10-YEAR EVENT AND A LOOK INTO THE FUTURE IS TROUBLING....

Observed Number of Extreme Precipitation Events



VILLAGE-WIDE SEWER INFRASTRUCTURE IMPROVEMENTS

Total investment since 1990 **\$78 MILLION**

COMBINED SEWER AREA

• Relief Sewers, Inlet Restrictors and Drainage Berms in the street to create temporary "street detention"

SEPARATE SEWER AREA

- Sanitary Relief Sewers
- Second Stormwater Outfall
- Backup Generator at Stormwater Pump Station

VILLAGE-WIDE MAINTENANCE

Sewer Cleaning/Televising/Lining

IDENTIFYING THE PROBLEM





- Highly developed land
- Designed without stormwater management practices
- Limited open space
- No defined overflow routes

IDENTIFYING THE PROBLEM





Bottleneck was insufficient storm sewer capacity



EXISTING CONDITIONS – 100-YR STORM



The blue shaded areas represent flooding

VILLAGE OF WILMETTE

STORMWATER ACTION PLAN

Figure A2 - 100-Year Existing Condition Flood Extents Storm Sewer Study Reduced Cost Analysis Village of Wilmette





THE RESULT: STRUCTURES AND PARCELS IMPACTED



Storm Event	Structures Impacted ¹	Parcels Flooded ²
10-year	311	1,268
100-year	1305	2,779

- 1. Flood water to within 1-foot of highest lot elevation
- 2. Flood water reaches private property
 - 5,444 total parcels west of Ridge

RESULT: WIDESPREAD FLOODING DURING RAIN EVENTS









Property damage



Anxiety and stress for homeowners



As long as 17 hours of standing water



Inaccessible streets



IDENTIFYING THE OPTIONS



SEPT 2013

The Village Board approved a contract with CBBEL for the Separate Storm Sewer Study.

The Village reviewed a number of potential projects which were deemed not cost effective or did not provide adequate flood relief including:

- Purchase of homes impacted by flooding
 Too costly and not effective
- Green infrastructure as the primary solution
 Green improvements can be complimentary to any project but are not sufficient as a stand-alone improvement to provide flood relief
- Nine different variations of conveyance and storage projects

IDENTIFYING THE OPTIONS



SEPT 2013	The Village Board approved a contract with CBBEL for the Separate Storm Sewer Study.
JAN 2017	The Village Board approved a contract with Stantec to conduct a technical and alternatives review.
DEC 2017	The Village Board narrowed the Options to three for final consideration.

THE OPTIONS





SEWER EXPANSION

• 8.3 miles of new storm sewer

2

SEWER EXPANSION & NEIGHBORHOOD STORAGE HYBRID

 5.4 miles of new storm sewer and stormwater storage at Thornwood Park



NEIGHBORHOOD STORAGE

 3.3 miles of new storm sewer and stormwater storage at Thornwood Park, Centennial Park and Hibbard Park



PUBLIC PROCESS TO BUILD TRUST AND CONSENSUS



Given the magnitude of the capital investment under consideration, the Village undertook an extensive public education campaign over a 4-month period:

- Sent three mailers to all Wilmette addresses (11,000+ addresses)
- Held two open houses with more than 100 residents attending
- 6,000 visitors reviewed the website dedicated to stormwater improvements
- Engaged the community through an online community portal
- Produced a public education video
- Received more than 300 email communications







PUBLIC PROCESS TO BUILD TRUST AND CONSENSUS



SEPT 2013	The Village Board approved a contract with CBBEL for the Separate Storm Sewer Study.
JAN 2017	The Village Board approved a contract with Stantec to conduct a technical and alternatives review.
DEC 2017	The Village Board narrowed the Options to three for final consideration.
APR 2018	The Village Board approved the Neighborhood Storage Project
	Storage Project

PROJECT DESIGN & CONSTRUCTION EXECUTION (2018 – 2022)



FEB 2019

The final optimized plan for Option 3 is approved

- 14 Million Gallons of Stormwater Storage in 3 Village Parks (21 Olympic Swimming Pools)
- 5 miles of storm sewer
- Cost Estimate = \$68M
- 98% protection level for 10-year event (305/311)
- Timeframe = 4 years
- Phases 1A 3







Internal Team













External Team & Partners



Wilmette PUBLIC SCHOOLS DISTRICT 39

Village Residents

PARTNERSHIPS – THE WILMETTE PARK DISTRICT



The fundamental concept of the Neighborhood Storage Project was to store excess runoff in locations near where it fell. It was determined that 3 parks within the Village (and owned by the Wilmette Park District) were suitable:

- Community Playfield (Phase 1 Construction 2020)
 - Largest park within the Village and region
 - Heavily used for athletics (soccer, baseball, others)
 - Located between Highcrest Middle School and Wilmette Junior High
- Hibbard Park (Phase 2 Construction 2021)
 - Located immediately adjacent to Community Recreation Center
 - Future expansion potential for building expansion
 - Baseball and soccer uses
- Thornwood Park (Phase 3 Construction 2022)
 - Dedicated little league baseball organization and neighborhood group
 - Located across the street from Harper Elementary School



Stormtrap Underground Vault System

PHASE 1 & COMMUNITY PLAYFIELD CONSTRUCTION YEAR 2020



- Project Features
 - Storage Volume = 20.3 Acre-ft
 - 18.6 acre-ft flood control
 - 1.7 acre-ft stormwater detention
 - 2,300 Stormtrap pieces
 - 5,800 linear feet of storm sewers
- Design Challenges:
 - Storage Vault Located on Park District Property between two schools
 - Largest of all the vaults
 - Largest Park and Open Space in region – nearly 40 acres
 - 3 Easements and 2 IGAs required



PHASE 1 – COMMUNITY PLAYFIELD





PHASE 1 – COMMUNITY PLAYFIELD PARK DISTRICT PARTNERSHIP



- Onsite and Park District Board Meetings
- Tree Removal was biggest issue Cottonwood Grove
- Field grading and inlet structure locations
- Multiple alternatives analyzed
- Disruption of Park Use During Construction
- Park Amenities (IGA)
 - Tree preservation plans with vault layouts incorporated into IGA and Easements
 - Specific drainage improvements at Community Playfield
 - Drainage improvements outside of work zone
 - Comprehensive Landscaping Plan (all 3 parks)
 - Irrigation (2 parks*)
 - Public Restrooms (2 parks*)
 - Recreational Path with Lighting (1 park)
- Total Cost of IGA = \$3.4M for all 3 parks





PHASE 1 – COMMUNITY PLAYFIELD FINAL DESIGN





- 3.5 acre footprint
- Gravity drained
- Height of StormTrap = 6-7 feet
- 2 trees to be removed



PHASE 1 - SCHOOL DISTRICT 39 PARTNERSHIP



- Phase 1 Flood Storage at Community Playfield
- Location is landlocked between two schools and residential properties
- Small portion of vault and storm sewer on school property



Access route through Highcrest Middle School Parking Lot



This was the largest Stormtrap vault in Illinois by number of pieces (2,300)



An estimated 50,000 cubic yards of soil needed to be removed, requiring 200 trucks/day

SCHOOL DISTRICT 39 COORDINATION



- Components of IGA included:
 - Access Plans (Early, Full, Late) for Summer construction
 - Fencing and dust control during construction
 - Existing stormwater detention on school property was put underground as part of new vault
 - Driveway improvements
 - Temporary air conditioning at Highcrest School for dust prevention
 - New entry sign for school
 - New wireless communication system
 between schools
 - Vibration monitoring along haul route



Late Access



WORK ZONE COMPLIFELY FENCED OFF (6-FOOT AND CHAIN LINK) AND BLACKED OUT. STE SECURED AT THE END OF EACH WORK DAY. CONSTRUCTION ANTICIPATED 7 DAYS A WEEK WITH EXTENDED HOURS AS APPROVED BY THE VILLAGE BOARD.

NULLAGE TO ADD PROVISIONS FOR SUPPLEMENTAL SITE WATERING.

IF NECESSARY, TO CONTROL DUST DURING CONSTRUCTION. COMMUNITY PLAYFIELD WITHIN THE CONSTRUCTION ZONE WILL BE OUT OF USE UNTIL SPRING 2021 TO ALLOW THE SOD TO ESTABLIST

PHASE 1 – COMMUNITY PLAYFIELD CONSTRUCTION STARTS APRIL 2020

- Berger Construction \$12M
 - StormTrap installation and park restoration
 - Storm sewers 5,800 linear feet
- StormTrap Contract \$5M
- Total Phase 1 Cost \$17M
- Impacts (Benefits) of Covid
 - All Coordination Virtual
 - Construction Production Plan and H&S Plan
 - Virtual School Opened Construction Window (silver lining)
- Excavation
 - 1,630,000 ft³ of soil removed
 - 6,000 truck loads of material hauled
 - 200+ trucks/day
- StormTrap
 - 25+ trucks/day from April August
 - Second largest vault in Illinois by volume
 - Largest by number of pieces
 - Total 20.2 acre-ft of stormwater storage
 - 6.5 Million Gallons
 - 10 Olympic Size Swimming Pools







PHASE 1 – COMMUNITY PLAYFIELD CONSTRUCTION COMPLETE OCTOBER 2020





PHASE 2 – HIBBARD PARK CONSTRUCTION YEAR 2021



- Project Features
 - Storage Volume = 10.0 Acre-ft
 - 550 Stormtrap pieces
 - 6,900 linear feet of storm sewers in neighborhood
 - Stormwater pump station
 - De-water vault in 24 hours
- Design Challenges
 - Storage Vault Located entirely on Park District Property
 - Mature trees around Park
 perimeter
 - Space Restrictions
 - Park District Plans for Expanded Community Rec Center



PHASE 2 – HIBBARD PARK PARK DISTRICT COORDINATION



- On-site and Park District Board Meetings
- Tree Removal was biggest issue
- Future Considerations of Community Rec Center footprint must be honored
- Limited space for construction staging
- Multiple Layouts Evaluated
 - Trees Removed
 - Stormtrap Vault Depth
 - Field Layouts
- Park Amenities included in IGA
 - Drainage Improvements
 - Restoration of Fields
 - Location Drainage Structures in Fields
 - Comprehensive Landscaping Plan





PHASE 2 – HIBBARD PARK FINAL DESIGN





Cross-Section of Pump Station and Hill Street Storm Sewer



- 1 acre footprint
- Height of StormTrap = 15 feet
- Pump Station, Backup Generator and Landscaping
- Detailed access and tree fencing plan
- 6 trees removed

PHASE 2 – HIBBARD PARK CONSTRUCTION STARTS FEB 2021

- V3 Companies \$10.2M
 - StormTrap installation and park restoration
 - Storm sewers 6,900 linear feet
 - Pump Station
- StormTrap Contract \$1.6M
- Total Phase 2 Cost \$11.8M
- Excavation
 - 1,000,000 ft^3 of soil removed
 - 3,700 truck loads of material hauled
 - 100 trucks/day (tight footprint)
- StormTrap
 - 15+ trucks/day
 - Tallest Vault in Illinois at the time
 - Total 10 acre-ft of stormwater storage
 - 3.2 Million Gallons
 - 5 Olympic Size Swimming Pools









StormTrap Installation



PHASE 2 – HIBBARD PARK CONSTRUCTION COMPLETE SEPTEMBER 2021





PHASE 3 – THORNWOOD PARK CONSTRUCTION YEAR 2022



- Project Features
 - Storage Volume = 13.6 Acre-ft
 - 716 Stormtrap pieces
 - 7,500 linear feet of storm sewers in neighborhood
 - Stormwater pump station
 - De-water vault in 24 hours
- Design Challenges
 - Storage Vault Located entirely on Park District Property
 - Mature trees around Park perimeter
 - Space Restrictions in Park
 - Very active neighborhood group
 - Adjacent to Harper Elementary School
 - Narrow Roadways
 - Construction along school walking routes



PHASE 3 – THORNWOOD PARK PARK DISTRICT COORDINATION

- On-Site and Park District Board Meetings
- Critical issue is tree removal
 - Mature trees throughout park
 - Multiple layouts evaluated
 - Construction Fence Alignment
 - Construction Access Locations
- Two little league baseball fields
 - Baseball Field Restoration
 - No Impact to backstops, bleachers, etc
- Pump Station location in park
 - Permanent access for Village
- Ice rink relocation and enhancements
- Construction Timing







PHASE 3 – THORNWOOD PARK FINAL DESIGN





Cross-Section of Pump Station and Thornwood Avenue Storm Sewer – Looking West



- 1.5 acre footprint
- Height of StormTrap = 15 feet
- Pump Station, Backup Generator and Landscaping
- Detailed access and tree fencing plan
- 2 trees removed

AN EVOLVING STRATEGY FOR RESIDENT ENGAGEMENT.....



- 1 Virtual Meeting
- 2 On-site Open House Style Meetings
- Resident Concerns
 - Pump Station location and screening
 - Seed vs sod restoration
 - Generator Permanent vs. Portable
 - Tree Preservation
 - Roadway Construction and Parking
 - Construction Schedule
 - School Traffic and walking routes
 - Safety due to Proximity of School



CRITICAL ISSUE - DETAILED STAGING PLAN REQUIRED FOR PHASE 3



Safety was primary driving factor since Thornwood Park was adjacent to a school and this project reconstructed adjacent roadways – the School Walking Route Map was used as the base map to develop the five (5) stages of construction

- Summer construction:
 - Thornwood Park
 - Hunter Road main school walking route
 - Critical intersection Hunter and Lake
- Heavy hauling routes
- Contractor capacity issues
- Detailed MOT and walking routes for each stage
- Start of each stage depended on successful completion of previous stage
- A well choreographed ballet



EXAMPLE STAGING PLAN





- How kids walk/ride bikes to school
- Construction flaggers at entrances to Thornwood Park
- Flaggers and temporary pavement at cross-walks along school walking routes
- Specifics for teacher parking on adjacent streets
- No large trucks on adjacent streets during school pick-up and drop off times

RESIDENT COORDINATION EVOLVED INTO A TRUE PARTNERSHIP





PHASE 3 – THORNWOOD PARK CONSTRUCTION STARTS APRIL 2022



- Berger Excavating \$18.7M
 - StormTrap installation and park restoration
 - Storm sewers 7,900 linear feet
 - Pump Station
- StormTrap Contract \$2.2M
- Total Phase 3 Cost \$20.9M
- Excavation
 - 1,300,000 ft³ of soil removed
 - 4,700 truck loads
 - 125 trucks/day (tight footprint)
- StormTrap
 - 15+ trucks/day
 - Total 13.6 acre-ft of stormwater storage
 - 4.4 Million Gallons
 - 6.75 Olympic Size Swimming Pools



PHASE 3 – THORNWOOD PARK CONSTRUCTION COMPLETE NOVEMBER 2022





THIS WAS THE LARGEST CAPITAL PROJECT IN WILMETTE'S HISTORY THAT INCLUDED:

PHASE 1 – COMMUNITY PLAYFIELDS

- Second Largest in Illinois by volume
- · 2307 pieces most pieces in Illinois
- 20.2 acre-ft of stormwater storage
 6.5 Million Gallons

10 Olympic Size swimming pools

HIBBARD PARK

- First 15-foot-tall vault in Illinois
- 10 acre-ft of stormwater storage

3.2 million gallons

فی کی کی د

5 Olympic size swimming pools

THORNWOOD PARK

13.6 acre-ft of stormwater storage
 4.4 Million gallons



6.75 Olympic size swimming pools



5 MILES OF STORM SEWER INSTALLED OVER 50 PUBLIC MEETINGS THE TOTAL PROJECT COST WAS \$64M

