



Building Communities.
Improving Lives.



Mahoney Creek Watershed Planning and Project Implementation in Batavia, Illinois

IAFSM 2023 | Tinley Park | Session 5A (1:30 – 3:00)




Agenda

- Project location and timeline
- History of the area and stream
- Project need
- Mahoney Creek stream assessment
- Watershed Based Planning
- Project Implementation
- Next Steps



Project Location

- Mahoney Creek is tributary to the Fox River
- The watershed is nearly entirely contained within the City
- Total watershed is 2.03 sq. mi.
- The Mahoney Creek Tributary is the only large tributary to the stream



Project Timeline


- 2008: A study of the Mahoney Creek Tributary was completed
- 2018: A conceptual plan for adding detention was completed and property acquired
- 2019: HR Green brought on to assist with a stream assessment
- 2020: Mahoney Creek Stream Assessment completed
- 2021: Design of Mahoney Creek Tributary Detention Basins is completed
- 2022: Mahoney Creek Watershed Based Plan submitted
- 2022: Construction of the Mahoney Creek Tributary Detention Basins completed
- 2023: Pursuit of grant funding for future projects



Mahoney Creek Watershed Planning and
Project Implementation
Batavia, Illinois


History of the area and streams - 1840

- The state of Illinois published plat maps from 1840. 180 years ago the area was identified as “Timber” or what is now referred to as “Savanna or Woodland”
- The Mahoney Creek Tributary was not identified



History of the area and streams - 1939

- The historic stream alignment is outlined in orange
- The City has been established
- Much of the timber land has been converted to farm land



History of the area and streams – 2020's

- Over time the stream has been moved and channelized
- The historic stream alignment is outlined in orange
- The current day stream is shown in blue
- Most of the watershed is residential or industrial
- Online detention and stormwater easements placed on the stream




Project Need

- Assess the current condition of Mahoney Creek and the Mahoney Creek Tributary
- Identify potential improvements to the waterway and adjacent land
- Prioritize projects based on need, accessibility and funding
- How do we handle nuisance flooding reports
- Concern over future map updates or new FIRMs along the Mahoney Creek Tributary




Mahoney Creek Stream Assessment

- The stream was broken into 17 reaches
- Each reach was assessed by an ecologist and an engineer.
- Ratings were assigned based on numerous characteristics of the stream and surrounding vegetation.



Mahoney Creek Stream Assessment



Mahoney Creek Stream Assessment

City of Batavia
Illinois

Legend

Erosion Severity

- Major
- Minor
- Moderate


- City Roads
- County Roads
- State Roads
- Township Roads

MC_## Mahoney Creek Reach ID

MCT_## Mahoney Creek Tributary Reach ID



Data Source:
Coordinate System: NAD 1983 StatePlane Illinois East FIPS 1201 Feet
Projection: Transverse Mercator
Datum: North American 1983
Units: Foot US



Mahoney Creek Stream Assessment

Reach MC_03



Reach MC_01



Reach MC_10



Reach MC_07



Reach MC_04



Reach MC_05



Mahoney Creek Stream Assessment

Reach MC_01



Reach MC_01



Reach MC_10



Reach MCT_03



Reach MC_05



Reach MC_05




Mahoney Creek Stream Assessment



Mahoney Creek Stream Assessment

- Online survey
 - 442 surveys sent out
 - 68 responded
 - 1/3 of the residents who lived on the stream responded
- Zoom public meetings
- Final meeting was in person



HRGreen®

Mahoney Creek Watershed Planning and Project Implementation

Batavia, Illinois

Watershed Based Planning

- Residents were concerned with ecological health
- Having an approved WBP improves odds of grant funding
- IEPA watershed based plan was submitted for review in spring 2022



Project Implementation


• Mahoney Creek Tributary Detention Basins

- A previous study conceptualized adding detention at the headwaters of the Mahoney Creek Tributary
- The City had been planning this project, including land acquisition
- Existing channel was downcutting and the headcut had reached Kirk Road
- Property had thick honeysuckle and buckthorn brush with mature trees
- Bank erosion was significant
- Lots of coordination with Fermi Lab and KDOT
- Timing was critical due to the Northern Long Eared Bat



Mahoney Creek Watershed Planning and
Project Implementation
Batavia, Illinois

Project Implementation



- Both ponds restored with native vegetation
- Trees and screening incorporated in the west pond

Project Implementation

- The project was bid with a base bid and 2 alternatives
- 9 bids were received in total
 - EOPC = \$1,193,503
 - Bids ranges from \$1,255,218 to a low bid of \$815,500
 - City chose to forego Bid Alternative #2
 - V3 Construction Group was awarded the project
- The City's total investment into the Mahoney Creek Tributary
 - Contract amount = \$932,879
 - Actual amount = \$808,103
- Extensive coordination with the Department of Energy (Fermi Lab) was required to construct Bid Alternative #1



Mahoney Creek Watershed Planning and
Project Implementation
Batavia, Illinois

Project Implementation



Project Implementation



Project Implementation



Project Implementation



Project Implementation



Project Implementation



3/28/2023

Project Implementation



3/28/2023

Project Implementation



3/28/2023

Project Implementation



3/28/2023

Project Implementation



3/28/2023

Lessons Learned

- Coordinating with a federal agency such as the DOE can take time.
- COVID was a challenge!
- Communication with residents prior to construction is key to community support.
 - Tree removal notifications
 - Many people working from home watching construction closely
 - Future projects the City will use a posted sign with project information
- Educating residents about proper maintenance of stream banks (no mowing, no dumping, etc.) is effective
- Alderman support was critical



Mahoney Creek Watershed Planning and
Project Implementation
Batavia, Illinois

Next Steps

- City is planning additional projects along the waterways
- Plan to pursue GIGO and Section 319 grant funding
- Potential bank stabilization projects
- Residential education is on-going



Questions



Andrea Podraza, P.E., CFM
Assistant City Engineer – City of Batavia
200 Raddant Road | Batavia | IL
630.454.2757
apodraza@cityofbatavia.net

Logan Gilbertsen, P.E., CFM
Project Manager – Water Resources
323 Alana Drive | New Lenox | IL
815.759.8370
lgilbertsen@hrgreen.com



Mahoney Creek Watershed Planning and
Project Implementation
Batavia, Illinois