Success and Lessons Learnt, 7th Avenue Creek City of St. Charles, IL



IAFSM - 2022




AGENDA

- PROJECT HISTORY
- EXISTING CONDITIONS
- PROPOSED DESIGN
- LESSONS LEARNT
- PROJECT PHOTOS




PROJECT LOCATION





PROJECT LOCATION





PROJECT HISTORY


- 2008 Flooding!
- 2009 FEMA study results in increased BFE
- 2009 to 2014 FEMA remapping process underway
- 2014 HR Green was hired to prepare flood mitigation plan
- 2015 FEMA Preliminary Maps Issued
- 2016 Master Plan is completed
- 2018 7th Avenue Creek / State Street Creek Watershed-Based Plan
- 2018 CLOMR applied for based on proposed improvements
- 2018/19 Section 319 and GIGO grants obtained
- 2020 FEMA Maps becomes effective
- 2021 Construction of Phase 1 completed

2008 RAIN EVENT





EXISTING VS. PROPOSED FLOODPLAIN





TWO CONCURRENT & PARALLEL PATHS





PROJECT OBJECTIVES

FEMA

Flood Risk Mapping (FEMA)

CITY

- Flood Mitigation (reduce below regulatory floodplain)
- Improve Aesthetics/Return Amenity to Residents
- Improve Water Quality
- Explore Funding
- Consider City's Comprehensive Plan
- Consider Economic Development Opportunities



Many banks were highly eroded and threatening private property



Around this location we learned that Ajay's phone was waterproof. First Lesson Learnt




This structure was bought out and removed from the floodplain



Many retaining walls were removed to restore a natural channel. Quantification and pay items for these items need to be clearly defined.




PHASE I CONCEPT PLAN





PHASE I CONCEPT PLAN





Key Plan: Reach 5

Existing Photo




Draft: November 6, 2016








PHASE I FINAL PLAN





PHASE I FINAL PLAN

- The low flow channel was sized based on upstream and downstream stable sections
- The high flow channel and floodplain bench were sized for the 100-year event
- The low flow channel meanders within the high flow channel.
- Wherever possible, the multi-use trail was located above the 50-year WSE






FUNDING SUMMARY

- FEMA funded mapping revisions
- Obtained Riverboat Casino Grant
- Obtained 319 Grant for Phase I for eligible activities
- Obtained GIGO Grant for Phase I for eligible activities
- Phase I Completed (2021 construction)
- Total Construction Costs \$3.6M
- City's Share of Construction Cost (\$1.7M or 47.4%)
- NOW ON TO THE LESSONS LEARNED!




ENVIRONMENTAL CONTAMINATION





ENVIRONMENTAL CONTAMINATION





EARTHWORK CALCULATIONS

Earth excavation quantities can be tricky: Surface to surface to surface calculations – Ensure topsoil thickness is accounted for!



EARTHWORK CALCULATIONS

Lesson Learnt #3

Track how much quantity is rock excavation, channel excavation, earth excavation, topsoil excavation and respread.



EROSION CONTROL

Lesson Learnt #4

deleta Eletata

Consider how much "throw away" erosion control will be needed in plan quantities. Consider mulches for during construction and blankets for final stabilization



PREVENTING SEDIMENTATION W/I CULVERTS



Lesson Learnt #5

Culverts are often wider than the low flow channel, this leads to decreased velocity in the non-dominant barrels and insufficient ability to keep sediment suspended \rightarrow Siltation occurs

03/17/2020

Success and Lessons Learnt, 7th Avenue Creek | St. Charles, IL



24

PREVENTING SEDIMENTATION W/I CULVERTS

A weir was constructed to reduce the risk of sedimentation within the second box. The second box only engages when the larger floodplain bench is flowing



PREVENTING SEDIMENTATION W/I CULVERTS





MEANDER DESIGN

Meander Design Methodology:

- Spreadsheet tools;
- o Radius of Curvature;
- Meander Length;
- o Belt Width;
- Sinuosity;
- Wetted Width;
- Channel Slope;
- Stone used on the outer bends
- Vegetation used on inside bend



















Landscaping outcropping recycled from a boughtout property was used around the pedestrian bridge.


















































BEFORE AND AFTER STREAM CORRIDOR







FLAGSTONE AND BOULDERS REUSE





PROJECT COMPLETION – 2021





PROJECT COMPLETION – 2021











QUESTIONS FROM THE AUDIENCE

Ajay Jain, P.E., CFM Project Manager ajain@hrgreen.com 815-759-8331

Logan Gilbertsen, P.E., CFM Lead Engineer

lgilbertsen@hrgreen.com

815-759-8370

